

VERIFI® Sample Specification

SECTION 03300 - CAST-IN-PLACE CONCRETE

Metered Water Additions in Transit

Note to Specifier: ASTM C94/C94M was revised in 2013 to allow water additions during transit for trucks equipped with automated slump and water management systems. Check your specification to ensure it does not prohibit in-transit addition of water. Add the following text.

Water additions during transportation shall be made in accordance with ASTM C94/C94M.

Automated Quality Control and Quality Assurance

Note to Specifier:The following text defines minimum requirements for an automated slump management system for ensuring consistent quality concrete.

PART 1 - GENERAL

1.X Quality Control By Contractor

- Automated Slump Management System. Ready mix trucks shall be equipped with the VERIFI[®] Slump Management System (GCP Applied Technologies, www.gcpat.com, 62 Whittemore Ave Cambridge, MA 02140) or equivalent system capable of the following:
 - Monitor concrete slump to an accuracy of ± 1 in. (25 mm). The equipment shall obtain one or more physical measurements on the truck mixer related to concrete slump and provide an indication of slump based on pre-established correlations. Equipment shall be accurate for 50% to 100% of mixing drum volume capacity. Upon request, concrete supplier shall provide data no older than 24 months confirming the accuracy of calibration for each truck type.
 - Meter water added to the truck to an accuracy of $\pm 3\%$ of the amount added or ± 1 quart (1 liter), whichever is greater. Upon request, concrete supplier shall provide data no older than 12 months confirming the accuracy of calibration.
 - Meter admixture added to the truck to an accuracy of $\pm 3\%$ of the amount added or ± 1 quart (1 liter), whichever is greater. Upon request, concrete supplier shall provide data no older than 24 months confirming the accuracy of calibration.
 - Monitor concrete temperature to an accuracy of $\pm 2^{\circ}\text{F}$ (1°C). Upon request, concrete supplier shall provide data no older than 24 months confirming the accuracy of calibration.
 - Perform automated additions of water, admixture, or both to achieve a target slump.
 - Stop additions of water when reaching the maximum water content for the mixture design.
 - Provide the following via electronic means or visual display to an inspector upon request at the jobsite: concrete slump, concrete temperature, water added, admixture added, age, total revolutions, total revolutions at mixing speed since last water addition.
 - Provide the following via electronic means to the engineer: concrete slump, concrete temperature, water added, admixture added, age, total revolutions, total revolutions at mixing speed since last water addition. All data shall be for the start of discharge.

gcpat.com | North America customer service: 617-498-3858

GCP Applied Technologies Inc., 2325 Lakeview Parkway, Suite 400, Alpharetta, GA 30009, USA

GCP Canada, Inc., 294 Clements Road, West, Ajax, Ontario, Canada L1S 3C6

This document is only current as of the last updated date stated below and is valid only for use in the United States. It is important that you always refer to the currently available information at the URL below to provide the most current product information at the time of use. Additional literature such as Contractor Manuals, Technical Bulletins, Detail Drawings and detailing recommendations and other relevant documents are also available on www.gcpat.com. Information found on other websites must not be relied upon, as they may not be up-to-date or applicable to the conditions in your location and we do not accept any responsibility for their content. If there are any conflicts or if you need more information, please contact GCP Customer Service.

Last Updated: 2023-06-28

gcpat.com/solutions/products/verifi-transit-concrete-management/verifi-sample-specification